

ZECHE In House Sound System

Main Hall/ Last Update November 2007



1.) Main System

- 4x EV MTH 4/ rigged L + R under ceiling
- 6x EV MTL 4/ situated under stage

Nearfill

- 2x EV DML 1152 biamped/ rigged under ceiling/ separate feed from foh

Delay Line/ Balcony

- 2x EV DML 1152 biamped/ rigged under ceiling/ separate feed from foh

2.) FOH

- 1x Yamaha PM 3000/ 40 mono/ 4 stereo/ 8 sub/ 8 vca/ 8 matrix
- 2ch. EQ. Klark Teknik DN 300
- 8ch. Noise Gate BSS DPR 504
- 4ch. Compr. BSS DPR 402
- 4ch. Compr. DBX 160x
- 1x Digital Delay Roland SDD 330 + Tap
- 2x Multieffekt Yamaha SPX 900
- 1x Multieffekt Yamaha SPX 50D
- 1x Dig.Reverb Lexicon PCM 70
- 1x CD Sony

3.) Monitor

- 2x Sidefills EV 2x 18"/ 2x 12"/ 1x 2"/ triamped
- 8x Wedges EV FS 2122/ 2x 12"/ 1x 2"/ biamped
- 1x Drumfill Top EV DML 1152/ 1x 15"/ 1x 2"/ biamped
- 1x Drumfill Sub EV 2x 18"
- 1x PFL Wedge 1x 15"/ 1x 2"/ biamped
- 1x Soundcraft 500 48/12
- 8ch. EQ. Klark Teknik DN 300
- 8ch. Noise Gate BBT NG 01
- 4ch. Compr. DBX 166
- 1x Yamaha Rev 5

4.) Others:

- 1x Multicore System 48ch.
- 1x Standard Mic/ Di – Set (SM 57/ SM58/ B52/ C451+CK1/ MD521/ MD441/ e904/ etc.)
- 1x Standard - Accessory - Set (stands/ clamps & claws/ cables/ plug boxes/ etc.)
- 1x Intercom System ASL/ 3 pos. (foh/ mon./ lights)